

New London Harbor & ThamesRiver Project Segment	CY	Timeframe	Disposal Base Plan & Alternatives	Unit Cost per Cubic Yard	Total Cost	Difference from Base Plan
Maintenance of New London Harbor FNP 40-foot Main Channel - Access to Sub Base	393,000	2026-2030	New London DS	\$13	\$5,109,000	
			Central LIS DS	\$48	\$18,864,000	\$13,755,000
			Upland Site	\$127	\$49,911,000	\$44,802,000
			Island Building	\$141	\$55,413,000	\$50,304,000
Maintenance of Lower Thames River 40-Foot Channel - Access to Sub Base	832,000	2026-2030	New London DS	\$26	\$21,632,000	
			Central LIS DS	\$47	\$39,104,000	\$17,472,000
			Upland Site	\$125	\$104,000,000	\$82,368,000
Maintenance of US Navy Sub Base Berths	75,000	2016-2020	New London DS	\$31	\$2,325,000	
			Central LIS DS	\$64	\$4,800,000	\$2,475,000
			Upland Site	\$104	\$7,800,000	\$5,475,000
Improvement Dredging for US Navy Sub Base - in Phases (Initial Phase 65,000 CY)	350,000	2016-2025	New London DS	\$26	\$9,100,000	
			Central LIS DS	\$57	\$19,950,000	\$10,850,000
			Upland Site	\$123	\$43,050,000	\$33,950,000